

## SECTION 01018 - OWNER FURNISHED EQUIPMENT

### PART 1 - GENERAL

#### 1.1 DESCRIPTION

A. Equipment items listed at the end of this Section and indicated on the Drawings as Owner- Furnished shall be purchased directly by the Owner. Owner's and Contractor's responsibilities concerning these items are as follows:

1. Owner's Responsibilities:
  - a. Arrange for and deliver necessary shop drawings, product data and samples to the Contractor.
  - b. Arrange and pay for Product delivery to the site, in accordance with the Construction Schedule.
  - c. Deliver supplier's bill of materials to Contractor.
  - d. Inspect deliveries jointly with Contractor.
  - e. Submit claims for transportation damage.
  - f. Arrange for replacement of damaged, defective or missing items.
  - g. Arrange for manufacturer's warranties, bonds, service, inspections as required.
2. Contractor's Responsibilities:
  - a. Designate delivery date for each product in the Construction Schedule.
  - b. Review drawings, product data and samples.
  - c. Submit to Architect/Engineer with notification of any discrepancies or problems anticipated in the use of the product.
  - d. Receive and unload products at the site.
  - e. Promptly inspect products jointly with Owner, record shortages, damaged or defective items.
  - f. Handle products at the site, including uncrating and storage.
  - g. Protect products from exposure to elements, from damage.
  - h. Assemble, install, connect, adjust and finish products, as stipulated in the respective sections of specifications.
  - i. Repair or replace items damaged by Contractor.
  - j. Arrange for testing of all Owner-Furnished equipment.

3. 1.2

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION



- A. These remarks do not replace, supersede, or exempt any requirements contained in the specification Sections or the Drawings. Applicable remarks numbers appear in List of Owner-Furnished items.

1.3 GENERAL REMARKS

1. See Supplementary Notes.
2. See Hospital Systems section for detailed layouts and specifications.
3. Rough-in only.
4. Existing item - to be relocated from present location.

STRUCTURAL REMARKS

5. Contractor supplies and installs hoist support.
6. Contractor installs ceiling support and special control box (as required) supplied by Owner.
7. Contractor supplies slab plus electric and gas service.
8. Contractor prepares floor.
9. Contractor supplies backing and installs mounting brackets/hardware as required. Mounting brackets/hardware supplied by Owner.
10. Contractor installs rough-in frames and flange.

MECHANICAL REMARKS

11. Ventilation - make-up air required.
12. Ventilation - exhaust required.

PLUMBING REMARKS

13. Contractor installs stand-by valve supplied by Owner.
14. Contractor installs filters supplied by Owner.
15. Contractor installs mixing valve supplied by Owner.
16. Requires Water supply.
17. Required Steam supply.
18. Requires distilled or deionized water supply.
19. Requires drain.
20. Requires gas supply.
21. Requires compressed air supply.
22. Requires vacuum.
23. Contractor furnishes and installs all piping and provides pressure test for purging system.

ELECTRICAL REMARKS

24. Contractor supplies and installs wiring for safelight and wiring between bin limit switch and overhead darkroom lights.
25. Contractor supplies and installs interconnecting wire to remote alarm in PBX.
26. Contractor supplies and supplies conduit, standard AC wiring and standard backboxes.
27. Contractor installs special wire, cable and back boxes supplied by Owner.
28. Contractor supplies and installs conduit, troughs, power, wiring, etc., noted on drawings. All other wiring by Owner.
29. Requires isolated power supply.
30. Requires equip potential groundings.
31. Requires 3-phase power supply.
32. Power consumption greater than 2 kilowatts.
33. Contractor furnishes and installs all conduit, standard backboxes, blocking, backboards, power outlets and electrical rough-in, and installs special backboxes furnished by Owner.

Contractor furnishes and installs all blocking, wiring or electrical rough-ins.